

NOT FOR CONSTRUCTION

SAN JOAQUIN COUNTY
BE-WELL BEHAVIORAL HEALTH CAMPUS

HMH / KMD ARCHITECTS
COUNTY PROJECT # - SJC-PDB-HCSA

- B. Engage a factory-authorized service representative to adjust door closing devices, compensating for final operation of heating and ventilating equipment, and to comply with referenced accessibility requirements.
- C. Follow-up Adjustment: Approximately 6 months after date of Substantial Completion, Installer shall perform the following:
 - 1. Examine and readjust each item of door hardware as necessary to ensure function of door hardware.
 - 2. Consult with and instruct Owner's personnel on recommended maintenance procedures.
 - 3. Replace door hardware items that have deteriorated or failed due to faulty design, materials, or installation of door hardware units.

3.10 FIELD INSPECTIONS

- A. Fire Door Assembly Inspection and Testing: Provide functional testing and inspection of fire door assemblies in accordance with current NFPA 80. Inspections shall be performed by individuals certified by Intertek as a Fire Door Assembly Inspector (FDAI), using reporting forms provided by the Door and Hardware Institute (DHI). Alternatively, inspections may be performed by individuals acceptable to the Architect, who have knowledge and understanding of the operating components of the applicable door type, and who have experience in preparing written reports of testing and inspection results.
 - 1. Schedule fire door assembly inspection within 90 days of Substantial Completion of the Project.
 - 2. Submit a signed, written final report as specified in Paragraph 1.03.K: Submittals.
 - 3. Contractor shall correct all deficiencies and schedule a reinspection of fire door assemblies which were noted as deficient on the inspection report.
 - 4. Inspector shall reinspect fire door assemblies after repairs are made.
 - 5. Additional reinspections which are required due to incomplete repairs will be performed by the inspector at the expense of the Contractor.

3.11 FIELD QUALITY CONTROL

- B. Independent Architectural Hardware Consultant:
 - 1. Engage a qualified independent Architectural Hardware Consultant to perform inspections and to prepare inspection reports.
 - 2. Independent Architectural Hardware Consultant shall inspect door hardware and prepare written report whether installed work complies with or deviates from requirements, whether door hardware is properly installed and adjusted, and prepare a specific list of any deficiencies, a copy of which shall be provided to Architect.
 - 3. Contractor shall correct all deficiencies noted in above report.
 - 4. Independent Architectural Hardware Consultant shall re-inspect door hardware and prepare a report certifying correction of deficiencies and compliance with requirements.

NOT FOR CONSTRUCTION

SAN JOAQUIN COUNTY
BE-WELL BEHAVIORAL HEALTH CAMPUS

HMH / KMD ARCHITECTS
COUNTY PROJECT # - SJC-PDB-HCSA

3.12 COMPLETION

- A. When complete all hardware shall be properly secured in place and all exposed surfaces shall be clean and free from scratches, paint, and other defects and damages.
- B. Contractor shall demonstrate that all keys properly operate the locks as identified in the approved Keying Schedule.

3.13 DOOR HARDWARE SETS

- A. The following is a general listing of hardware requirements. Provide hardware items required by established standards and practices to meet state and local codes, whether or not specifically indicated in the following sets.
- B. Silencers and gasketing, where listed in Hardware Sets, may be omitted at openings where door frames are provided with integral seals if integral seals satisfy all applicable Codes and Regulations.
- C. Refer to Door Schedule and/ or Drawings for door opening information, hardware set assignment, and related requirements.
- D. Door protection items -- mop plates, kick plates, armor plates, and edge guards -- are not indicated in Hardware Sets. Refer to Door Schedule and/ or Drawings for required locations.

-- Remainder of page intentionally left blank --

NOT FOR CONSTRUCTION

SAN JOAQUIN COUNTY
BE-WELL BEHAVIORAL HEALTH CAMPUS

HMH / KMD ARCHITECTS
COUNTY PROJECT # - SJC-PDB-HCSA

Note: Where possible, it is recommended to remove door closers on high-risk areas per NYS OMH standards.

HW 01 Interior Single Bedroom - Classroom Lock/Ligature Resistant - No Closer - Rescue Hdw

Each Opening to Receive:

High Risk

<u>Quantity</u>	<u>Description</u>	<u>Model Number</u>	<u>Finish</u>	<u>Manf</u>
1 Set	Continuous Hinge-Double Acting	A508	630	ABH
1 Ea.	Ligature Res. Mortise Lock-Classrm	MRX-A-05	630	TOW
1 Ea.	Cylinder	Per project	630	TBD
1 Ea.	Door Stop	1841	630	ABH
1 Set	Gasketing	ANTI-LIG 5050	BLK	NGP
1 Ea.	Emergency Rescue Stop	A509	630	ABH

HW 02 Interior Single - Office Lockset/Ligature Resistant - No Closer - Continuous Hinge

Each Opening to Receive:

Medium Risk

<u>Quantity</u>	<u>Description</u>	<u>Model Number</u>	<u>Finish</u>	<u>Manf</u>
1 Set	Continuous Hinge	AC500 HT SEC	630	ABH
1 Ea.	Ligature Res. Cyl. Lock-Office	CRX-A-81	630	TOW
1 Ea.	Cylinder	Per project	630	TBD
1 Ea.	Door Stop	1841	630	ABH
1 Set	Gasketing	ANTI-LIG 5050	BLK	NGP

HW 02A Interior Single - Office Lock/Ligature Resistant - Surface Closer/Track-Arm - Cont Hinge

Each Opening to Receive:

Medium Risk

<u>Quantity</u>	<u>Description</u>	<u>Model Number</u>	<u>Finish</u>	<u>Manf</u>
1 Set	Continuous Hinge	AC500 HT SEC	630	ABH
1 Ea.	Ligature Res. Cyl. Lock-Office	CRX-A-81	630	TOW
1 Ea.	Cylinder	Per project	630	TBD
1 Ea.	OH Surface Closer - Track Arm	4210T/4510T TRX mount on public side	689	LCN
1 Ea.	Door Stop	1841	630	ABH
1 Set	Gasketing	ANTI-LIG 5050	BLK	NGP

HW 03 Interior Single - Storeroom Lock/Ligature Resistant - Surface Closer/Track-Arm - Cont Hng

Each Opening to Receive:

Medium Risk

<u>Quantity</u>	<u>Description</u>	<u>Model Number</u>	<u>Finish</u>	<u>Manf</u>
1 Set	Continuous Hinge	AC500 HT SEC	630	ABH
1 Ea.	Ligature Res. Cyl. Lock-Storerm	CRX-A-86	630	TOW
1 Ea.	Cylinder	Per project	630	TBD
1 Ea.	OH Surface Closer - Track Arm	4040XPT TROX	689	LCN
1 Ea.	Door Stop	1841	630	ABH
1 Set	Gasketing	ANTI-LIG 5050	BLK	NGP

NOT FOR CONSTRUCTION

SAN JOAQUIN COUNTY
BE-WELL BEHAVIORAL HEALTH CAMPUS

HMH / KMD ARCHITECTS
COUNTY PROJECT # - SJC-PDB-HCSA

HW 04 Interior Single - Storeroom Lockset/Ligature Resistant - Surface Closer - Continuous Hng

Each Opening to Receive: Medium Risk

<u>Quantity</u>	<u>Description</u>	<u>Model Number</u>	<u>Finish</u>	<u>Manf</u>
1 Set	Continuous Hinge	AC500 HT SEC	630	ABH
1 Ea.	Ligature Res. Cyl. Lock-Storerm	CRX-A-86	630	TOW
1 Ea.	Cylinder	Per project	630	TBD
1 Ea.	OH Surface Closer	4210T/4510T TBTRX mount public side	689	LCN
1 Ea.	Door Stop	1841	630	ABH
1 Set	Gasketing	ANTI-LIG 5050	BLK	NGP

HW 04A Interior Single - Storeroom Lockset/Ligature Resistant - Surface Closer - Continuous Hng

Each Opening to Receive: Medium Risk

<u>Quantity</u>	<u>Description</u>	<u>Model Number</u>	<u>Finish</u>	<u>Manf</u>
1 Set	Continuous Hinge	AC500 HT SEC	630	ABH
1 Ea.	Ligature Res. Cyl. Lock-Storerm	CRX-A-86	630	TOW
1 Ea.	Cylinder	Per project	630	TBD
1 Ea.	OH Surface Closer	4040XPT BUMP Torx	689	LCN
1 Set	Gasketing	ANTI-LIG 5050	BLK	NGP

HW 05 Interior Single - Storeroom Lockset - Surface Closer - Butt Hinges

Each Opening to Receive: N203 (Low Risk)

<u>Quantity</u>	<u>Description</u>	<u>Model Number</u>	<u>Finish</u>	<u>Manf</u>
As Req	Hinge-HT	CB51 HT	630	PBB
1 Ea.	Cyl. Lock-Storerm	CDC-86-S	626	TOW
1 Ea.	Cylinder	Per project	626	TBD
1 Ea.	OH Surface Closer	4040XP/4040XP EDA	689	LCN
1 Ea.	Door Stop	Per Specification	---	---
1 Set	Gasketing	5050	BLK	NGP

HW 05A Interior Single - Storeroom Lockset - No Closer - Butt Hinges

Each Opening to Receive: Low Risk

<u>Quantity</u>	<u>Description</u>	<u>Model Number</u>	<u>Finish</u>	<u>Manf</u>
As Req	Hinge-HT	CB51 HT	630	PBB
1 Ea.	Cyl. Lock-Storerm	CDC-86-S	626	TOW
1 Ea.	Cylinder	Per project	626	TBD
1 Ea.	Door Stop	Per Specification	---	---
1 Set	Gasketing	5050	BLK	NGP

NOT FOR CONSTRUCTION

SAN JOAQUIN COUNTY
BE-WELL BEHAVIORAL HEALTH CAMPUS

HMH / KMD ARCHITECTS
COUNTY PROJECT # - SJC-PDB-HCSA

HW 06 Interior Single - Card Reader - Elec Fail-Secure Lock - Surface Closer - Butt Hinges

Each Opening to Receive:		N112A		
<u>Quantity</u>	<u>Description</u>	<u>Model Number</u>	<u>Finish</u>	<u>Manf</u>
As Req	Hinge-HT	CB51 HT	630	PBB
1 Ea.	Hinge-Power Transfer	CB51EL HT	630	PBB
1 Ea.	Fail Secure Cyl. Lock	XCDC-86-S-RQE Fail Secure 24VDC	626	TOW
1 Ea.	Cylinder	Per project	626	TBD
1 Ea.	OH Surface Closer	4040XP/4040XP EDA	689	LCN
1 Ea.	Door Stop	Per Specification	---	---
1 Set	Gasketing	5050	BLK	NGP
1 Ea.	Card Reader	By Division 28	---	---
1 Ea.	Door Position Switch	By Division 28	---	---
1 Ea.	Lock Power Supply	By Division 28	---	---

Note: Controlled Opening - Card Reader, Wiring, Controls, Power, and other components by Security. Free egress at all times. ~~Power Supply require 120VAC.~~

Note: Fail Secure - Upon loss of power lock becomes locked. Door remains latched. Secure side remains unlocked for egress. Unsecure side remains locked.

HW 06A Moved to Exterior Set HW E11**HW 07 Interior Single - Institutional Privacy/Occ Ind - Ligature Resistant - Self Closing Cont Hinge**

Each Opening to Receive:		High Risk - Patient RR		
<u>Quantity</u>	<u>Description</u>	<u>Model Number</u>	<u>Finish</u>	<u>Manf</u>
1 Set	Self Closing Continuous Hinge	A507SC HT	628	ABH
1 Ea.	Ligature Res Mort Lock-Ins.Privacy/ID	MRX-A-26-O	630	TOW
1 Ea.	Cylinder	Per project	630	TBD
1 Ea.	OH Concealed Closer	2031 Torx	689	LCN
1 Ea.	Door Stop	1841	630	ABH
1 Set	Gasketing	ANTI-LIG 5050	BLK	NGP

Note: NYS OMH Standards do not approve any door closers for High Risk areas. Closer removed.

HW 07A Interior Single - Storeroom Privacy w/ID&Override - Ligature Resistant - SRCL - Cont Hinge

Each Opening to Receive:		Medium Risk		
<u>Quantity</u>	<u>Description</u>	<u>Model Number</u>	<u>Finish</u>	<u>Manf</u>
1 Set	Continuous Hinge	AC500 HT SEC	630	ABH
1 Ea.	Lig Res Mortise Lock-Strm Priv w/ID	MRX-A-15-O (Storerm Prvy W/ID ORD)	630	TOW
1 Ea.	Cylinder	Per project	630	TBD
1 Ea.	OH Surface Closer	4210T/4510T TBTRX mount on public side	689	LCN
1 Ea.	OH Concealed Closer	2031 BUMP	689	LCN
1 Ea.	Door Stop	1841	630	ABH
1 Set	Gasketing	ANTI-LIG 5050	BLK	NGP